

## Laying & Burial

2006

### JAKASUSI project ( fibre-optic cable )

The aim of the JAKASUSI project for ASN was the installation of the Jakasusi Separate Shore End Fiber Optic cables ( segment B1 and B2 ) in Banyu Urip / East Java and Takesung / Kalimantan in July and August 2006.

Scope of work was the following :

- Collection of cable lengths at Singapore port
- Shore ends laying and burial up to 1.20 m : for the following locations
  - Banyu Urip / Java : 12700 m
  - Takesung / Kalimantan ( segment to Java - Banyu Urip ) : 9700 m
  - Takesung / Kalimantan ( segment to Sulawesi ) : 10700 m
  - Total cable length : 33100 m

For this installation work, LD TRAVOCEAN has used a specific spread dedicated to the work. The installation spread was supported by one logistic and accommodation barge "Promoter 12" and TVO3 shallow draft pontoon fitted as a cable laying and burial spread.

TVO3 was fitted with the following equipment :

- Cable tank taking into account the cable min. bending radius
- LCE
- Cable way and cable chute and necessary equipment
- All necessary rigging and posit system
- EBJ 04 jetting spread for soft soil conditions



**Etablissement  
de  
Marseille**

Les Docks Atrium 10-4  
10, place de la Joliette - B.P. 64344  
13567 Marseille Cedex 02 FRANCE

Tel. +33 (0)4 91 04 42 00  
Fax. +33 (0)4 91 33 85 05  
E-mail: ldtravocean@ldtravocean.com